

Executive Engineer
ಲೆಕ್ಕ ಅಧೀಕ್ಷಕರು ಕಾ.ಪಂ.ಅ.ಸಿ.ಎಂ ಯಾಲಹನಕೆ ವಲಯಕ್ಕೆ

Sl. No.	Description of item	Unit
	Name of Work :- Annual Maintenance and repairs of street lights in ward no 04 Package Y -04 of Yelahanka Zone	
1	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for 36/40 W fluorescent tube light street lighting	Each
2	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for 125 W HPMV light Park lighting systems.	Each
3	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for 250W HPSV street light lighting systems.	Each
4	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents 400 watts HPSV street light/High Mast lighting systems.	Each
5	Operation and Maintenance of LED Street lighting system including replacement of damaged/failed/fused out compnents like LED drivers MCPCB surge protective device switches, Wires Holders, Staters observing weather proofing technic confirming to IP 65 standards and switching ON/OFF of Street lights at specified timing and pole numbering. Preparing ward wise Street wise Street light data bank furnishing maintenance reports every day etc., complete so as to ansure efficient burning of Street lights detailed in Tender documents for 24 watt LED park lighting systems.	Each
6	Operation and Maintenance of LED Street lighting system including replacement of damaged/failed/fused out compnents like LED drivers MCPCB surge protective device switches, Wires Holders, Staters observing weather proofing technic confirming to IP 65 standards and switching ON/OFF of Street lights at specified timing and pole numbering. Preparing ward wise Street wise Street light data bank furnishing maintenance reports every day etc., complete so as to ansure efficient burning of Street lights detailed in Tender documents for 65 watt LED street light lighting systems.	Each
7	Operation and Maintenance of LED Street lighting system including replacement of damaged/failed/fused out compnents like LED drivers MCPCB surge protective device switches, Wires Holders, Staters observing weather proofing technic confirming to IP 65 standards and switching ON/OFF of Street lights at specified timing and pole numbering. Preparing ward wise Street wise Street light data bank furnishing maintenance reports every day etc., complete so as to ansure efficient burning of Street lights detailed in Tender documents for 90 watt LED street light lighting systems.	Each
8	Operation and Maintenance of LED Street lighting system including replacement of damaged/failed/fused out compnents like LED drivers MCPCB surge protective device switches, Wires Holders, Staters observing weather proofing technic confirming to IP 65 standards and switching ON/OFF of Street lights at specified timing and pole numbering. Preparing ward wise Street wise Street light data bank furnishing maintenance reports every day etc., complete so as to ansure efficient burning of Street lights detailed in Tender documents for 110/120 watt LED streetlight lighting system	Each

Previous Measurement		Present Measurement			Total Upto Date		Remarks
Qty.	Cost	Qty.	Rate Rs. P.	Amount	Qty	Cost	
		1	Months		Upto Date paid so for 26 Months		
0	0	0	57.12	0.00	0	0.00	
0	0.00	0	63.02	0.00	0	0.00	
2136x25 Months	4536330.00	2136	84.95	181453.20	2136x26 Months	4717783.20	
202x25 Months	225844.08	0	93.17	0.00	202x26 Months	225844.08	
0	0.00	0	73.33	0.00	0	0.00	
98x25 Months	233142.00	98	95.16	9325.68	98x26 Months	242467.68	
1034x25 Months	2967580.00	1034	114.80	118703.20	1034x26 Months	3086283.20	
163 x25 Months	52519.60	16	131.30	2100.78	163 x26 Months	54620.38	

CFC
Assistant Executive Engineer (Ele)
BBMP, Bangalore

9	Operation and Maintenance of LED Street lighting system including replacement of damaged/failed/fused out compnents like LED drivers MCPCB surge protective device switches, Wires Holders, Staters observing weather proofing technic confirming to IP 65 standards and switching ON/OFF of Street lights at specified timing and pole numbering. Preparing ward wise Street wise Street light data bank furnishing maintenance reports every day etc., complete so as to ansure efficient burning of Street lights detailed in Tender documents for 150 watt LED street light /High mast lighting system	Each
10	Painting of existing street light pole after scrapping the old paint and painted with suitable colour enamel/Silver paint including coping/footing of the pole.Upto 5Mtr street light pole.	Nos
11	Painting of existing street light pole after scrapping the old paint and painted with suitable colour enamel/Silver paint including coping/footing of the pole.8Mtr and above street light pole.	Nos
12	Supplying and fixing Moulded Case Circuit Breaker (MCCB) over the existing wood/panel board using necessary screws, bolts, nuts, necessary phase separators, handle and wiring complete. Protection of Overload and Short circuit with thermal Magnetic/Micro processor release and Earth Fault as per IS-13947. (lcu = lcs) 100Amps 25kA.	Each
13	Supply and Installation / Fixing / Provision of Pole box with HRC Fuse / MCB provision and suitable connector / terminal for 3 Ph / 1 Ph connections with Loop-In & Loop- Out terminals for 10 Sqmm / 25 Sqmm 3.5 C Al/Ar / Cu/ Ar Cable and branch out 2.5 Sqmm 2 core Al/Cu PVC Insulated cable, enclosed in a Thermoplastic, Polystyrene enclosure, which should be shock proof, safe, IP65(Weather Proof), rust proof, dust proof, water proof having Internally Embedded Gasket with provision for cable entry through IP65 Thermoplastic, polyamide glands and/or grommets.260mmx210mmx116mm	Each
14	Supply of LED floodlight luminaire with pressure die cast aluminium housing body for optimal thermal dissipation. Lamp compartment comprising of anti glare clear diffuser with Injection moulded polycarbonate/clear glass material, delivering superior light output. Rated life Burning Hrs 50000 hr @ Lumen Maintenance of 70%, CCT > 5500K, IP 66 optical and electrical compartment & impact resistance of complete luminaire > IK08. Power Factor >0.9 with mains,. LED Efficiency>130lm/w, nominal CRI >75. Luminaire manufacturer should have in- house facility accredited by NABL/CPRI & any Government certified agency & Design & Development facility certified by ISO 9001:2008 . Housing with supplier word mark /name shall be Engraved / Embossing on the die cast housing/ Body part. Warranty of 2 Years against any manufacturing defect working under standard electrical conditions as mentioned above should be given by LED manufacturer & Cree/Nichia/ Lumileds/Osram make LED Source.LED Floodlight 240W	Nos
15	Supplying and fixing angle iron frame work fabricated out of M.S. angle iron.. and M.S. flat ... with bolts, washers etc., and painted with 2 coats of red oxide and then two coats of approved paint. 40x40x6mm	Mtr
16	Supply and fixing of 4pole power contactor with NO/NC contacts on existing wood/panel board using necessary bolts, nuts, washers and wiring etc., complete with AC-3 Rating and as per IS-13947.100 to 125Amps	Nos
17	Supplying and fixing Microprocessor Based Astronomical timer Switch with using necessary bolts, nuts and washers.	Each
18	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898. 50-63 Amps SP	Each
	TOTAL	
	Add GST 18 % = 12%+6% on item no 1-9	0.00
	Total Rs item no 10-20	
	Add GST 18 % on item no 10-18	
	TOTAL Rs	
	Fine imposed for non burning of street lights For the period of 1/05/2024 to 31/05/2024	
	As per street light agreement clause 2% will be deducted in monthly maintenance bill against the released scrap material	
	GRAND TOTAL	

Certificate

- 1 The above said monthly maintenance work has been carried out satisfactorily
- 2 This Bill amount has not been claimed in any previous bills.

Assistant Executive Engineer (EE)
BBMP, Bangalore

0	0.00 ✓	0 ✓	155.95 ✓	0.00 ✓	0	0.00 ✓	
0	0.00 ✓	0 ✓	550.00 ✓	0.00 ✓	0.00	0.00 ✓	
235	180950.00 ✓	0 ✓	770.00 ✓	0.00 ✓	235.00	180950.00 ✓	
38	172140.00 ✓	0 ✓	4530.00 ✓	0.00 ✓	38.00	172140.00 ✓	
36	73944.00 ✓	0 ✓	2054.00 ✓	0.00 ✓	36.00	73944.00 ✓	
46	846400.00 ✓	0 ✓	18400.00 ✓	0.00 ✓	46.00	846400.00 ✓	
50.00	12750.00 ✓	0 ✓	255.00 ✓	0.00 ✓	50.00	12750.00 ✓	
20.00	144000.00 ✓	0 ✓	7200.00 ✓	0.00 ✓	20.00	144000.00 ✓	
20	80600.00 ✓	0 ✓	4030.00 ✓	0.00 ✓	20.00	80600.00 ✓	
28	20244.00 ✓	0 ✓	723.00 ✓	0.00	28.00	20244.00 ✓	
	9546443.68 ✓			311582.86 ✓		9858026.54 ✓	
	258260.85 ✓	-12%	37389.94 ✓	274192.92 ✓		270225.63 ✓	
		18%	49354.73 ✓	323547.65 ✓			
				0.00 ✓			
	121507.02 ✓			0.00 ✓		121507.02 ✓	
	9926211.55 ✓			323547.65 ✓		10249759.19 ✓	
	90500.00 ✓			3000.00 ✓		93500.00 ✓	
	163419.16 ✓			6470.95 ✓		169890.11 ✓	
	9672292.39 ✓			314076.69 ✓		9986369.08 ✓	

CFC
[Signature]
 11/6/14
 Assistant Executive Engineer (Elec)
 BBMP, Bangalore